

(Note: Edit these specifications to fit your project detail. Samples and estimating examples are available through www.SnoGuard.com, e-mail sales@SnoGuard.com or call 708.485-6272.)

Section 07710 Prefabricated Roof Specialties

(Gough SnoGuard Type SGAR Specification Sheet for Asphalt Shingles)

PART 1 – GENERAL REQUIREMENTS

1.01 SUMMARY

A. DESCRIPTION OF WORK

1. Install Gough SnoGuard Type SGAR snow guards for asphalt shingle roofs.
2. Assure proper positioning of snow guards with roof installation.
3. Use proper fasteners for mechanical attachment.

B. RELATED SECTIONS

1. Section 07600: Flashing and Sheet Metal
2. Section 07310: Roofing Shingles
3. Section 07710: Prefabricated Roof Specialties
4. Division 7: Thermal and Moisture Protection.

1.02 SUBMITTALS

- A. **PRODUCT DATA:** Submit manufacturer's product data & installation instructions.
- B. **SHOP DRAWINGS:** If not clearly shown on project drawings, submit roof drawing showing locations of all Gough SnoGuard Type SGAR snow guards and attachment spacing.
- C. **SAMPLES:** Submit sample of one Type SGAR snow guard as requested.

1.03 QUALITY ASSURANCE:

- A. **INSTALLER:** Installer is to be experienced in the installation of specified roofing material and snow guards for not less than 5 years in the area of the project.
- B. **FASTENERS:** Should be selected for compatibility with snow guard and roof deck.
- C. **CODE COMPLIANCE:** Comply with all applicable local, state, and national building codes, as well as OSHA regulations.
- D. **STORAGE:** Boxes containing Gough SnoGuards should be stored in a dry place until ready for use.

PART 2 – PRODUCTS

2.1 MANUFACTURER

- A. Gough SnoGuards, 4133 Du Bois Blvd., Brookfield, IL 60513-1809, voice (708) 485-6272, fax (708) 485-6273, e-mail: Sales@SnoGuard.com, Web Site: www.SnoGuard.com

2.2 MATERIAL

- A. 24 oz. cold rolled copper
- B. With double pedestal

2.3 FINISH

- A. Copper

PART 3 - EXECUTION

3.01 EXAMINATION

- A. **Substrate:** Inspect roof system to be properly attached and installed to withstand additional loading incurred. Notify General Contractor of any deficiencies before installing Gough SnoGuards.

3.02 INSTALLATION

- A. Comply with architectural drawings for placement & Manufacturer's instructions for installation.¹